## **CLEVELAND PUBLIC LIBRARY**

Finance Committee December 16, 2014

## RESOLUTION RATIFYING REPLACEMENT OF WATER LINE AT LAKESHORE FACILITY

- WHEREAS, The Property Management Department became aware this Fall that the main water line connected to the fire hydrants and fire sprinklers at the Lakeshore Facility of the Cleveland Public Library was leaking; and
- WHEREAS, As a result, the Library was compelled to perform emergency repairs and hired V.A. Conkey Company to perform the work. V.A. Conkey has submitted an invoice in the amount of \$28,965.09 for supplying the labor, equipment and material to locate the leak, excavate and replace 100 feet of an eight inch fire main; and
- WHEREAS, The Executive Director hereby requests that the Board of Library Trustees ratify the agreement with V.A. Conkey Company and authorize the expenditure of funds in the amount of \$28,965.09 for the necessary repairs; now therefore be it
- RESOLVED, That the Board of Library Trustees hereby ratifies and approves the agreement with V.A. Conkey Company, and authorizes the expenditure of funds in the amount of \$28,965.09 for the necessary emergency repairs. The expenditure shall be charged to the General Fund account 12100053-53310 Building Repair.



Terms

30 Days

P.O. No.

 $\tilde{s}_{j}$ 

V.A. CONKEY COMPANY PHONE: 440-269-5555 FAX: 440-269-1355

## RECEIVED FINANCIAL SERVICES

**Invoice** 

Date	Invoice #	and a second
12/1/2014	3398	

Bill To Cleveland Public Library 325 Superior Avenue Cleveland, Ohio 44114 Tim Murdock

Service Date	Description	Service	Amount
	Excavator, loader, and shoring Trucking Pipe, Fittings, and stone	Labor Equipment Material Material	9,280.00 3,800.00 2,530.00 13,355.09
	LAKESHORE - MAIN WATER LINES FOR FIRE HYDRANI AND INSIDE FIRE SPRINKLETES.	5	

Page 2

\$28,965.09

**Total** 



## Invoice

− ′- Dafe ′′ Cc	invoice #	
12/1/2014	3398	

Bill To	
Cleveland Public Library 325 Superior Avenue Cleveland, Ohio 44114 Tim Murdock	

Service Date	Description	Service	Amount
	17109 Lakeshore Blvd Fire Main Repairs		
11/3/2014	Supply labor and equipment to excavate in the rear of the property to attempt to locate a leak by an isolation valve feeding a fire hydrant. Found the valve was half turned on and this gave bad results on the leak detector locate. Advise location		
11/4/2014	company and had area re surveyed. Supply labor and equipment to work with the leak detection company to locate various leaks in a (100') stretch of 8" fire main.	• • • • • • • • • • • • • • • • • • •	. · · •4.
11/5/2014	Supply labor and equipment to saw cut pavement and remove for piping replacement.		
11/7/2014	Supply labor, equipment, and material to replace sections (100') of 8" fire main.		
11/10/2014	Supply labor, equipment, and material to replace sections (100') of 8" fire main.		
11/11/2014	Supply labor and equipment to backfill and compact the area. All piping backfilled with #57 Limestones. Pavement areas backfilled with #304 limestones to the surface. Removed all spoils off site.		
11/12/2014	Supply labor and equipment to finish removal of spoils. Demobilized all equipment.		